



# PRI Construction Materials Technologies LLC

6412 Badger Drive  
Tampa, FL 33610  
813.621.5777  
<https://www.pri-group.com/>

## Laboratory Test Report

**Report for:** Andrew Carpenter  
Mainstream Engineering  
200 Yellow Place  
Rockledge, FL 32955

The name has changed to QwikPad, see addendum attached.

**Product Name:** QwikHurricane® Pad  
**Project No.:** MAIN-001-02-01  
**Date(s) Tested:** Sep. 12, 2018 – Mar. 21, 2019  
**Test Method(s):** ASTM G155 (with ASTM D638)  
**Results Summary:** Refer to Results table

**Purpose:** Evaluate durability property for a plastic material, herein referred to as QwikHurricane Pad, in accordance with ASTM G155: *Standard Practice for Operating Xenon Arc Light Apparatus for Exposure of Non-Metallic Materials*.

**Test Methods:** Testing was conducted as requested by proponent. Test specimens were subjected to accelerated weathering described in ASTM G155-13: *Standard Practice for Operating Xenon Arc Light Apparatus for Exposure of Non-Metallic Materials*. Exposure parameters were in accordance with Cycle 1; exposure duration was 4,500h. Briefly, xenon arc lamp with Daylight filter was operating with irradiance setting of 0.35 W/m<sup>2</sup>-nm as measured at 340nm; cycle was 102min light exposure at 63±2.5°C Black Panel Temperature followed by 18min light and water spray (temperature not controlled). Test specimens were visually inspected for cracking or checking on the plastic surface.

Tensile Properties were assessed for unexposed (i.e. control) and exposed specimens. Tensile Properties were determined in accordance with ASTM D638-14: *Standard Test Method for Tensile Properties of Plastics*. Tensile Strength and Elongation at Break are reported.

**Sampling:** The following materials were received by PRI.

<u>Product</u>	<u>Source</u>	<u>Date</u>	<u>Sampling</u>
QwikHurricane Pad	Rockledge	Jun. 14, 2018	Mainstream Engineering

Manufacture location for product tested has been verified as Rockledge, FL.

**Conditioning:** All conditioning was completed in accordance with specification details.

### MAIN-001-02-01

The test results, opinions, or interpretations are based on the material supplied by the client. This report is for the exclusive use of stated client. No reproduction or facsimile in any form can be made without the client's permission. This report shall not be reproduced except in full without the written approval of this laboratory. PRI Construction Materials Technologies LLC assumes no responsibility nor makes a performance or warranty statement for this material or products and processes containing this material in connection with this report.

**Results:**  
**ASTM G155 (with ASTM D638)**

Physical Properties	Test Method	Results							Requirement <sup>1</sup>
Accelerated Weathering, [Pass/Fail] specimens; 1in x 9in Condition ASTM G155, Cycle 1 Visual Inspection	ASTM G155 Cycle 1	1			2				
After 4,500h ASTM G155, Cycle 1		Pass			Pass				There shall be no cracking or checking on the plastic surface
Tensile Strength, (psi) 5 specimens; Type IV x thickness Cond. 24h @ 73.4±3.6°F & 50±5%RH Test @ 73.4±3.6°F & 50±5%RH Rate = 2in/min	ASTM D638	1	2	3	4	5	Avg.	St.Dev.	
As Received Behavior = Yield		2,788	2,781	2,694	2,714	2,741	2,744	41	Report
After 4,500h ASTM G155, Cycle 1 Behavior = Yield		2,764	2,812	2,849	2,827	2,794	2,809	33	Report
Change (%)		+2.4%							±10%
Elongation at Break, (%) 5 specimens; Type IV x thickness Cond. 24h @ 73.4±3.6°F & 50±5%RH Test @ 73.4±3.6°F & 50±5%RH Rate = 2in/min	ASTM D638	1	2	3	4	5	Avg.	St.Dev.	
As Received Behavior = Yield		131.6	118.9	115.9	111.6	116.4	119	8	Report
After 4,500h ASTM G155, Cycle 1 Behavior = Yield		107.9	106.4	115.3	117.6	105.8	111	6	Report
Change (%)		-6.7%							±10%


Note(s): 1- indicates that Requirement listed is adopted from Miami-Dade Checklist #0445 (revised 9-1-12): Plastic and Foam Plastic

**MAIN-001-02-01**

The test results, opinions, or interpretations are based on the material supplied by the client. This report is for the exclusive use of stated client. No reproduction or facsimile in any form can be made without the client's permission. This report shall not be reproduced except in full without the written approval of this laboratory. PRI Construction Materials Technologies LLC assumes no responsibility nor makes a performance or warranty statement for this material or products and processes containing this material in connection with this report.

**Statement of Attestation:** The durability property of this material was evaluated in accordance with ASTM G155: *Standard Practice for Operating Xenon Arc Light Apparatus for Exposure of Non-Metallic Materials* with ASTM D638: *Standard Test Method for Tensile Properties of Plastics*. The laboratory test results presented in this report are representative of the material(s) tested.

Signed: \_\_\_\_\_  
  
Brad Grzybowski  
Managing Director

Signed: \_\_\_\_\_  
  
Duc T. Nguyen  
Florida Registered Professional Engineer  
P.E. Number: 65034


Date: \_\_\_\_\_  
03/26/2019

Date: \_\_\_\_\_  
3/27/2019

**Report Issue History:**

Issue #	Date	Pages	Revision Description (if applicable)
Draft	03/25/2019	3	NA
Original	03/26/2019	3	NA

END OF REPORT



**MAIN-001-02-01**

The test results, opinions, or interpretations are based on the material supplied by the client. This report is for the exclusive use of stated client. No reproduction or facsimile in any form can be made without the client's permission. This report shall not be reproduced except in full without the written approval of this laboratory. PRI Construction Materials Technologies LLC assumes no responsibility nor makes a performance or warranty statement for this material or products and processes containing this material in connection with this report.



## PRI Construction Materials Technologies LLC

6412 Badger Drive  
Tampa, FL 33647  
813.621.5777  
<https://www.pri-group.com/>

*Brad Grzybowski*  
Managing Director

April 24, 2024

Nicholas Nonnemacher  
Mainstream Engineering  
200 Yellow Place  
Rockledge, FL 32955

PRI-CMT provided third-party, independent testing and subsequently issued Laboratory Test Report(s). You have asked for a **Letter Addendum for PRI Report No. MAIN-001-02-01, issued 03/26/2019**, to recognize a change of Product Name. PRI completed ASTM G155 (with ASTM D638) testing for a plastic material, which at the time of testing and report issuance was identified as QwikHurricane® Pad.

**This Letter Addendum identifies Product Name as QwikPad®.** This recognition is based on the following:

1. Email request dated April 24, 2024 from Nicholas Nonnemacher with copy provided to Andrew Carpenter.

Signed: \_\_\_\_\_

Brad Grzybowski  
Managing Director

Date: \_\_\_\_\_

04/24/2019

MAIN-001-02-01